

## **ENERGY REPORT**

### **ENERGY ENGINEERING ANALYSIS PROGRAM**

### **ENERGY SAVINGS OPPORTUNITY SURVEY**

**FORT HUACHUCA, ARIZONA  
1994**

**VOLUME I**

19971016 219


**PREPARED FOR**

**DEPARTMENT OF THE ARMY  
SACRAMENTO DISTRICT, CORPS OF ENGINEERS  
SACRAMENTO, CALIFORNIA**

**PREPARED BY**

**KELLER & GANNON  
ENGINEERS • ARCHITECTS  
1453 MISSION STREET, SAN FRANCISCO, CA 94103**

**CONTRACT NO. DACA05-C-92-0155**



**DTIC QUALITY INSPECTED 2**




DEPARTMENT OF THE ARMY  
CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS  
P.O. BOX 9005  
CHAMPAIGN, ILLINOIS 61826-9005

REPLY TO  
ATTENTION OF: TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited.  
Distribution A. Approved for public release.

  
Marie Wakefield,  
Librarian Engineering

## **Table of Contents**

- 1.0 Executive Summary**
  - 1.1 Introduction**
  - 1.2 Energy Conservation Projects**
  - 1.3 Cogeneration Feasibility**
  - 1.4 Harmonic Distortion Survey**
- 2.0 Introduction**
  - 2.1 Purpose**
  - 2.2 Scope**
  - 2.3 Methodology**
- 3.0 Description of Installation**
  - 3.1 Location, Size and Climate**
  - 3.2 Electrical Power and Natural Gas Utilities**
  - 3.3 Central Heating/Cooling Plants**
- 4.0 Energy Conservation Retrofit Evaluations**
  - 4.1 Life Cycle Cost Analysis Assumptions**
  - 4.2 Construction Cost Estimate Methodology**
  - 4.3 Utility Rebate Programs**
  - 4.4 Energy Conservation Opportunities Studied**
  - 4.5 Recommended Energy Conservation Projects**
- 5.0 Harmonic Distortion Survey**
  - 5.1 Description of the Problem**
  - 5.2 Methodology and Data Summary**
  - 5.3 Evaluation and Recommendations**
- 6.0 Cogeneration Feasibility Evaluations**
  - 6.1 Natural Gas Piping Capacity**
  - 6.2 Turbine-Generator Facilities to Serve Central Heating/Cooling Plants**
  - 6.3 Engine-Generator Facilities to Serve Central Heating/Cooling Plants**
  - 6.4 Turbine-Generator Facilities to Serve Fort Huachuca and the City of Sierra Vista**
- APPENDIX**
  - A Scope of Work and Minutes of Project Meetings**
  - B Utility Rate and Rebate Schedules**
  - C Motor Survey Data and Retrofit Calculations**
  - D Natural Gas Cooling Retrofit Calculations**
  - E Building Envelope Retrofit Calculations**
  - F HVAC Controls Retrofit Calculations**
  - G Lighting Data and Energy Calculations**
  - H Lighting Retrofit Calculations**
  - I Harmonic Distortion Monitoring Data**
  - J Backup Data to Cogeneration Analyses**
  - K Carrier HAP Program Data**

## List of Figures

Figure 3-1	Fort Huachuca Location Map . . . . .	3-3
Figure 3-2	Fort Huachuca Historical Electrical Demand, March 1993 to March 1994: Maximum Daily kW . . . . .	3-4
Figure 3-3	Fort Huachuca Historical Electrical Demand for 1984 to 1994: Maximum Monthly kW . . . . .	3-5
Figure 3-4	Fort Huachuca Historical Power Factor for 1984 to 1994: Monthly Average Power Factor in Percent . . . . .	3-6
Figure 6-1	Combined Cycle Cogeneration, PURPA Qualifying Facility Flow Diagram . . . . .	6-7
Figure 6-2	Combined Cycle Exempt Wholesale Generation Flow Diagram . . . . .	6-7
Figure 6-3	Cogeneration Alternative 1C1: Ebullient Cooled Engine Generator with Heat Recovery and Single-Stage Absorption Chilling . . . . .	6-8
Figure 6-4	Cogeneration Alternative 1C2: Gas Engine Generator with Exhaust Heat Recovery and Two-Stage Absorption Chilling . . . . .	6-8
Figure 6-5	Cogeneration Alternative 1C3: Ebullient Cooled Engine Generator with Exhaust and Jacket Heat Recovery, One- and Two-Stage Absorption Chilling . . . . .	6-9

## List of Tables

Table 1-1	Project Group Summaries for Recommended ECOs . . . . .	1-3
Table 1-2	Summary of Life Cycle Cost Analyses for Central Heating/ Cooling Plant Cogenerative Alternatives . . . . .	1-5
Table 1-3	Summary of Life Cycle Cost Analyses for Power Generation Alternatives Serving Fort Huachuca and Sierra Vista . . . . .	1-6
Table 2-1	Potential ECO Evaluation List . . . . .	2-4
Table 4-1	Summary of Analysis Results for Recommended ECOs . . . . .	4-7
Table 4-2	Summary of Analysis Results for ECOs Not Recommended . . . . .	4-9
Table 4-3	Summary of Energy-Efficient Motor Retrofit Evaluations . . . . .	4-10
Table 4-4	Summary of Building Envelope Retrofit Evaluations . . . . .	4-11
Table 4-5	Summary of HVAC Controls Retrofit Evaluations . . . . .	4-12
Table 4-6	Summary of Lighting and Controls Retrofit Evaluations . . . . .	4-13
Table 5-1	Summary of Harmonic Distortion Monitoring Data . . . . .	5-4
Table 5-2	Comparison of Monitored Harmonics Levels with IEEE Guidelines . . . . .	5-5
Table 6-1	Summary of Life Cycle Cost Analyses of Cogeneration to Serve Central Heating/Cooling Plants . . . . .	6-10
Table 6-2	Summary of Life Cycle Cost Analyses of Power Generation to Serve Fort Huachuca and Sierra Vista . . . . .	6-11

## **1.0 Executive Summary**

### **1.1 Introduction**

This report summarizes all work performed for the Energy Engineering Analysis Program (EEAP) Energy Savings Opportunity Survey (ESOS) at Fort Huachuca, Arizona, authorized under Contract DACA05-92-C-0155 with the U.S. Army Corps of Engineers, Sacramento District, Sacramento, California.

The purpose of this study is to develop projects and actions that will reduce facilities energy consumption and operating costs at Fort Huachuca. Implementation of these projects will contribute to achieving the goal of the Army Facilities Energy Plan of a reduction in energy consumption per square foot of building floor area of 20 percent by FY2000 from FY1985 baseline levels.

The facility survey and evaluation effort was limited to 21 buildings and a specific set of energy conservation opportunities (ECOs) having a high likelihood of proving to be economically feasible. Also included were feasibility evaluations of cogeneration alternatives including (a) cogenerating alternatives serving the existing central heating/cooling plants, (b) a generating facility sized to serve the total electric power requirements of Fort Huachuca and (c) a generating facility sized to serve the total power requirements of both Fort Huachuca and the adjacent city of Sierra Vista. Both turbine generators and reciprocating-engine generators were evaluated for a cogeneration facility serving the two central heating/cooling plants.

Harmonic distortion sampling at four buildings containing significant computer loads or electronic fluorescent ballasts was also included in the study scope.

### **1.2 Energy Conservation Projects**

Successful ECOs were packaged into project groups containing similar trades in order to eliminate the extra charges associated with subcontractor services. A Work Request (EHSC Form 4283-1) was prepared for each project group. Each programming document included complete supporting data: retrofit descriptions, energy and cost savings calculations, construction cost estimates and life cycle cost analysis summaries. Data summaries for each of the project groups appear in Table 1-1.

Each of the following ECOs was found to be cost-effective in at least one of the buildings studied:

- Roof and wall insulation
- Low emissivity roof coating
- Replacing electric motor-driven chiller with gas engine-driven chiller
- Economizer and supply air temperature reset controls
- High-efficiency motor retrofits
- Lighting fixture and control retrofits

## **EEAP Energy Savings Opportunity Survey Fort Huachuca, Arizona**

### **1.3 Cogeneration Feasibility**

A number of cogeneration alternatives serving either one or both of the central heating/cooling plants and containing either gas turbine or gas-fired reciprocating engine prime movers were evaluated. A summary of life cycle cost analyses for these central heating/cooling plant cogeneration alternatives appears in Table 1-2. The recommended alternative, based on highest savings-to-investment ratio (SIR), is a cogeneration facility serving both central heating/cooling plants and containing ebullient-cooled gas-engine generators with single-stage absorption chilling and steam heat exchangers to provide chilled and hot water for building HVAC use.

A summary of life cycle cost analyses for power generation facilities sized to serve Fort Huachuca and the City of Sierra Vista appears in Table 1-3. Generation facilities of the sizes required to serve Fort Huachuca and Sierra Vista cannot be served from existing gas distribution on post or upstream from Southwest Gas Corporation's Fort Huachuca regulating station. Budget costs for installing gas supply piping from a point 4.5 miles from the potential generating facility site were included in the investment amount. However, an in-depth engineering analysis to determine the need for additional facilities must first be performed by Southwest Gas Corporation before the overall economic feasibility of a power generating plant serving Fort Huachuca and the City of Sierra Vista can be determined.

### **1.4 Harmonic Distortion Survey**

Harmonic distortion monitoring conducted at a representative sample of four buildings revealed that all measured voltage distortion levels were within the 5 percent recommended by ANSI/IEEE Standard 519. Current distortion percentages measured during early May were generally higher than those recommended by Standard 519, but are expected to fall within the guidelines during peak summer electrical demand periods when linear motor loads increase dramatically.

EEAP Energy Savings Opportunity Survey  
Fort Huachuca, Arizona

Table 1-1. Project Group Summaries for Recommended ECOs

Building or ECO Number	Retrofit Description	Energy Savings		Energy Cost Savings			O&M		Investment (\$)	Payback (Years)	SIR
		Electric (kW)	Electric (kWH/Year)	Gas (Million BTU/Yr)	Electric (\$/Year)	Gas (\$/Year)	Savings (\$/Year)	Rebate (\$)			
Building Envelope Modifications											
15544	Wall & Roof Insul + Low E Roof Coat	0.0	27,827	442	\$1,750	\$1,556	\$43,080	\$0	\$24,210	7.32	1.78
20200	Retrofit Roof Insulation	0.0	4,029	64	\$253	\$226	\$6,245	\$0	\$4,147	8.65	1.51
43083	Roof: Insulation & Low E	0.0	124,909	1,228	\$7,857	\$4,318	\$155,623	\$0	\$58,567	4.81	2.66
51005	Apply Low E Roof Coating	0.0	(14,401)	928	(\$906)	\$3,264	\$35,364	\$0	\$16,822	7.13	2.10
56301	Apply Low E Roof Coating	0.0	149,852	567	\$9,428	\$1,994	\$141,556	\$0	\$6,437	0.56	21.99
91114	Apply Low E Roof Coating	0.0	5,460	(16)	\$343	(\$57)	\$3,321	\$0	\$1,498	5.23	2.22
Subtotal, Building Envelope Modifications		0.0	297,676	3,214	\$18,724	\$11,301	\$385,191	\$0	\$111,681	3.72	3.45
Gas Engine-Driven Chiller Retrofit											
56301	Gas Engine-Driven Chiller - 72 Tons	67.0	267,690	(1,823)	\$21,508	(\$8,218)	\$142,078	(\$1,032)	\$122,512	9.99	1.06
Building HVAC Control Modifications and High Efficiency Motor Retrofits											
56301	Economizer Control & SA Reset @ OA Temp	0.0	382,501	28,726	\$1,577	\$1,443	\$39,403	\$0	\$16,548	5.48	2.38
15544	SA Fan HVAC Unit	1.2	10,783	0	\$679	\$0	\$10,235	\$0	\$1,356	2.00	7.55
43083	SA Fan AHU No. 1	0.2	2,068	0	\$130	\$0	\$1,963	\$0	\$476	3.66	4.12
43083	SA Fan AHU No. 2	0.2	2,068	0	\$130	\$0	\$1,963	\$0	\$476	3.66	4.12
56301	SA Fan, North HVAC Unit	0.3	2,246	0	\$141	\$0	\$2,132	\$0	\$578	4.09	3.69
56301	SA Fan, Central HVAC Unit	0.3	2,246	0	\$141	\$0	\$2,132	\$0	\$578	4.09	3.69
56301	SA Fan, South HVAC Unit	0.3	2,246	0	\$141	\$0	\$2,132	\$0	\$578	4.09	3.69
56301	CHW Circ. Pump 1	0.3	1,168	0	\$73	\$0	\$1,108	\$0	\$421	5.73	2.63
56301	CHW Circ. Pump 2	0.2	727	0	\$46	\$0	\$691	\$0	\$421	9.20	1.64
56301	Condenser Fan 1	0.2	661	0	\$46	\$0	\$694	\$0	\$476	10.35	1.46
56301	Condenser Fan 2	0.2	661	0	\$46	\$0	\$694	\$0	\$476	10.35	1.46
57305	CHW Circ. Pump 2	0.5	2,368	0	\$149	\$0	\$2,248	\$0	\$1,623	10.89	1.38
61701	Pool Circ. Pump	0.4	3,472	0	\$219	\$0	\$3,296	\$0	\$947	4.33	3.48
62704	SA Fan	0.6	4,974	0	\$313	\$0	\$4,721	\$0	\$1,091	3.48	4.33
62704	RA Fan	0.3	2,246	0	\$141	\$0	\$2,132	\$0	\$578	4.09	3.69
67601	AHU 1 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
67601	AHU 2 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
67601	AHU 3 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
67601	AHU 4 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
67601	AHU 5 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
67601	AHU 7 SA Fan	0.5	887	0	\$95	\$0	\$1,438	\$0	\$766	8.03	1.88
80505	SA Fan East	0.9	7,536	0	\$474	\$0	\$7,154	\$0	\$1,266	2.67	5.65
80505	SA Fan West	0.9	7,536	0	\$474	\$0	\$7,154	\$0	\$1,266	2.67	5.65



EEAP Energy Savings Opportunity Survey  
Fort Huachuca, Arizona

Table 1-1. Project Group Summaries for Recommended ECOs

Building or ECO Number	Retrofit Description	Electric (kW)	Electric (kWh/Year)	Gas (Million BTU/Yr)	Electric (\$/Year)	Gas (\$/Year)	LCC Savings (\$/Year)	O&M Savings (\$/Year)	Utility Rebate (\$)	Investment (\$)	Payback (Years)	SIR
80505	RA Fan East	0.4	3,226	0	\$203	\$0	\$3,062	\$0	\$56	\$578	2.85	5.30
80505	RA Fan West	0.4	3,226	0	\$203	\$0	\$3,062	\$0	\$56	\$578	2.85	5.30
80505	Fan Coil Unit, Rm 213	0.2	1,789	0	\$113	\$0	\$1,698	\$0	\$35	\$520	4.62	3.26
80505	HWP-1	0.3	1,459	0	\$92	\$0	\$1,385	\$0	\$46	\$476	5.19	2.91
80505	Fan Coil Unit, Rm 249	0.2	1,935	0	\$122	\$0	\$1,836	\$0	\$46	\$708	5.82	2.59
80505	CHWP-1	0.4	1,959	0	\$123	\$0	\$1,859	\$0	\$58	\$766	6.21	2.43
80505	CHWP-2	0.4	1,959	0	\$123	\$0	\$1,859	\$0	\$58	\$766	6.21	2.43
80505	VAVH2 West, Roof FCU	0.2	1,676	0	\$105	\$0	\$1,591	\$0	\$58	\$766	7.26	2.08
80505	VAVH2, Roof FCU	0.2	1,676	0	\$105	\$0	\$1,591	\$0	\$58	\$766	7.26	2.08
91114	HW Circ. Pump	0.3	1,439	0	\$91	\$0	\$1,368	\$0	\$17	\$421	4.65	3.24
Subtotal, Building HVAC Control Modifications and High Efficiency Motor Retrofits		13.2	461,172	28,726	\$6,775	\$1,443	\$117,789	\$0	\$1,778	\$40,098	4.88	2.94
Lighting Fixture and Control Retrofits												
Lights A	LED Exit Fixtures	108 EA	17,171	0	\$1,082	\$0	\$13,000	(\$165)	\$972	\$5,438	5.94	2.03
Lights B2	Ballasts/T8s 2xF30T12	124 EA	8,124	0	\$868	\$0	\$10,438	\$104	\$1,240	\$5,502	5.66	2.12
Lights D1	Ballasts/T8, 1xF40T12	120 EA	9,066	0	\$658	\$0	\$7,912	(\$136)	\$1,080	\$5,217	9.99	1.20
Lights D2	Ballasts/T8, 2xF40T12	1,401 EA	107,700	0	\$9,046	\$0	\$108,733	(\$48)	\$14,010	\$67,229	7.47	1.61
Lights D5	Delamp 4 to 3 T8s, Ballasts	671 EA	144,543	0	\$13,296	\$0	\$159,823	\$497	\$12,749	\$43,531	3.16	3.81
Lights E1	Ballasts 2 xF48T12HO	48 EA	5,491	0	\$468	\$0	\$5,625	\$0	\$192	\$2,107	4.50	2.67
Lights F1	Ballasts/T8, 2xF96T12	20 EA	1,872	0	\$183	\$0	\$2,317	(\$32)	\$200	\$1,822	11.35	1.06
Lights F2	Ballasts/T8, 4xF96T12	1 EA	166	0	\$18	\$0	\$220	(\$3)	\$20	\$182	11.73	1.03
Lights G1	DTT 13W CF-Downlights	2 EA	139	0	\$18	\$0	\$218	\$7	\$10	\$37	1.44	8.36
Lights G2	TRI 20W Compact Fluor.	24 EA	4,547	0	\$523	\$0	\$6,284	\$278	\$35	\$62	0.08	153.60
Lights G3	TT 7W Compact Fluor.	71 EA	4,488	0	\$519	\$0	\$6,239	\$246	\$225	\$1166	1.52	7.87
Lights G4	DTT 13W CF-Ceiling	45 EA	3,786	0	\$446	\$0	\$5,360	\$147	\$230	\$876	1.48	8.12
Lights G5	TRI 23W Compact Fluor.	28 EA	4,965	0	\$535	\$0	\$6,435	(\$88)	\$150	\$894	2.00	6.02
Lights H1	17W CF Table Lamps	249 EA	23,384	0	\$2,499	\$0	\$30,043	\$994	\$1,245	\$4,876	1.40	8.60
Lights J1	150W HPS & Ballast	33 EA	5,448	0	\$673	\$0	\$8,085	\$54	\$320	\$6,568	9.05	1.33
Lights J2	200W HPS & Ballast	54 EA	23,475	0	\$2,578	\$0	\$30,985	\$159	\$1,129	\$8,387	3.06	3.92
Lights K1	Ceiling PIR Controls	239 EA	162,912	0	\$7,877	\$0	\$94,679	\$1,678	\$1,784	\$79,611	8.33	1.44
Lights K3	Wall Switch PIR Controls	162 EA	35,138	0	\$1,699	\$0	\$20,421	\$416	\$768	\$17,829	8.43	1.42
Subtotal, Lighting Fixture and Control Retrofits		123.6	562,417	0	\$42,996	\$0	\$516,817	\$4,105	\$36,359	\$251,336	5.34	2.25
Totals for Successful ECOs (SIR's > 1.0)		203.8	1,588,955	30,117	\$90,003	\$4,526	\$1,161,876	\$3,073	\$38,137	\$525,627	5.39	2.28

5,442 + 30,117 = 35,559  
METSU  
F:\PROJECTS\1640313\WORD\FT-HUACH\JULS Table 1-1

**EEAP Energy Savings Opportunity Survey**  
**Fort Huachuca, Arizona**

**Table 1-2. Summary of Life Cycle Cost Analyses for  
Central Heating / Cooling Plant Cogeneration Alternatives**

		Description of Cogeneration Alternative	Power kW	Investment	Annual Cost Savings		SIR	Payback Years
					Energy \$/Year	Non-Energy \$/Year		
Alternative 1A1	\$2,923 / Kw	Gas <u>Turbine-Generator</u> Cogeneration Facility serving Fort Huachuca's South Central Heating/Cooling Plant.	3,312	\$9,682,629	\$961,462	(\$29,459)	1.16	10.39
Alternative 1A2	\$2,873 / Kw	Gas <u>Turbine-Generator</u> Cogeneration Facility serving Fort Huachuca's North Central Heating/Cooling Plant.	3,312	\$9,517,018	\$935,657	(\$29,059)	1.13	10.50
Alternative 1B	\$2,924 / kW	Gas <u>Turbine-Generator</u> Cogeneration Facility serving both South & North Central Heating/Cooling Plants.	4,727	\$13,821,209	\$1,610,329	\$1,396	1.51	8.58
Alternative 1C1	\$1,568 / kW	Gas <u>Engine-Generator</u> Cogeneration Facility serving both Central Heating/Cooling Plants: Ebullient Cooled, Single-Stage Absorption Chilling.	6,600	\$10,346,129	\$1,384,319	(\$29,531)	1.74	7.64
Alternative 1C2	\$1,654 / kW	Gas <u>Engine-Generator</u> Cogeneration Facility serving both Central Heating/Cooling Plants: Two-Stage Absorption Chilling.	8,800	\$14,559,263	\$1,915,853	(\$141,775)	1.55	8.21
Alternative 1C3	\$1,829 / kW	Gas <u>Engine-Generator</u> Cogeneration Facility serving both Central Heating/Cooling Plants: Ebullient Cooled, Single & Two-Stage Absorption Chilling.	5,500	\$10,059,783	\$1,186,046	\$4,348	1.60	8.45

**EEAP Energy Savings Opportunity Survey**  
**Fort Huachuca, Arizona**

**Table 1-3. Summary of Life Cycle Cost Analyses for  
Power Generation Alternatives Serving Fort Huachuca and Sierra Vista**

	Description of Cogeneration Alternative	Power kW	Investment	Annual Cost Savings			SIR	Payback Years
				Energy \$/Year	Non-Energy \$/Year			
Alternative 2 \$1,084 / kW	<u>Gas Turbine</u> Combined Cycle Cogeneration Facility serving Fort Huachuca <u>and</u> Sierra Vista. Power generated to match electric demand.	52,248	\$56,615,344	\$17,407,722	(\$1,237,129)		1.98	6.24
Alternative 3 \$1,718 / kW	<u>Gas Turbine</u> Combined Cycle Cogeneration Facility serving Fort Huachuca <u>only</u> . Power generation to match electric demand.	22,248	\$38,215,478	\$7,349,328	(\$481,712)		1.39	9.19
Alternative 2 Max \$1,084 / kW	<u>Gas Turbine</u> Combined Cycle Cogeneration Facility serving Fort Huachuca <u>and</u> Sierra Vista. Power generated at plant capacity with excess power sales through the grid.	52,248	\$56,615,344	\$22,514,378	(\$1,799,860)		1.89	5.88
Alternative 3 Max \$1,718 / kW	<u>Gas Turbine</u> Combined Cycle Cogeneration Facility serving Fort Huachuca <u>only</u> . Power generated at plant capacity with excess power sales through the grid.	22,248	\$38,215,478	\$9,911,580	(\$766,408)		1.54	7.83